

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 147 - 20271-00-00 (of this well)
Lease Owner Baird Oil Company
Address Box 7, Logan, KS 67646
Lease (Farm Name) McCONNELL Well No. 1
Well Location N/2 S/2 SE/4 Sec. 26 Twp. 4S Rge. (28) 20 (W)
County Phillips Total Depth 3332' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 1:45 a.m., 5-8-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Wayne Shively Address 229 S. 11th Street, Wakeeney, KS 67672

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Baird Oil Company

Address Box 7, Logan, Kansas 67646

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Asst. Sec.-Treas.
Date: May 27, 1980

RECEIVED
JUN - 2 1980
CONSERVATION DIVISION
WICHITA, KANSAS
6-2-80

19-147-20271-06-00

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	McConnell #1
LOCATION:	N/2 S/2 SE/4, Section 26-4S-20W, Phillips County, Kansas
SPUD DATE:	4-29-80
COMPLETION DATE:	5-8-80

0	1490	Sand & Shale
1490	3332	Shale & Lime
	3332	Rotary Total Depth

Spud at 11:45 p.m., 4-29-80. Drilled 258' of 12-1/4" hole. Ran 6 joints of 8-5/8" 20# casing. (Tally 248.22) Set at 254.72'. Cemented with 175 sacks of common, 2% gel, 3% Ca.Cl. Plug was down at 5:30 a.m., 4-30-80. Cement did circ.

T.D.3332'. Set 1st plug at 840' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug 40' solid bridge with 10 sacks, and rathole with 5 sacks. 50/50 posmix, 6% gel. Job complete at 1:45 a.m., 5-8-80.

SAMPLE TOPS:

Anhydrite 1490'
B/Anhydrite 1521'

RECEIVED
STATE OF KANSAS
JUN - 2 1980
COMMISSIONER OF REVENUE
TOPEKA, KANSAS

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

62-80


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the McCONNELL #1, N/2 S/2 SE/4, Section 26-4S-20W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 27th day of May, 1980.

Sherrie L. Brooks
Sherrie L. Brooks, Notary Public



State of Kansas



15-147-20271-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 14, 1980

WELL PLUGGING AUTHORITY

McConnell Well No. 1
N/2 S/2 SE, Sec. 26-4S-20W
Phillips County
3332'
Abercrombie Drlg. Co., Inc.


Baird Oil Company
P.O. Box 7
Logan, KS 67648

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS 67601

is hereby assigned to supervise the plugging of the above named well