

15-039-20104-00-00 #4

API NUMBER 9-1-69

LEASE NAME Kasper

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

SPOT LOCATION SE SE SW

SEC. 4 TWP. 4 RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 9-1-69

Plugging Commenced 12-6-89

Plugging Completed 12-6-89

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	224	8 5/8		
	Casing	0	3779	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Rig up Petro Jet 2 shots at 1475' Run 2438' tubing. Rig up Halliburton and pump 40 sks. 65/35 pos. 10% gel, 2% diesel with 200# hulls. Pull tbg. to 1224'. Pump 40 sks. 65/35 10% gel, 2% diesel with 200# hulls. Pull tubing. Hook up to casing pump 10 sks. 65/35 pos, 10% gel, 2% diesel pressure to 600#. Shut in at 600#. Hook to annulus and pump 125 sks. 65/35 pos, 10% gel, 2% diesel with 100# hull. Shut in at 100#.


Name of Plugging Contractor Okmar Oil Company License No. 5245  
 Address Box 723 Hays, Kansas 67601

Halliburton cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Mo. 67601



SUBSCRIBED AND SWORN TO before me this 8 day of December, 1989

Rosemary Smith  
 Notary Public

My Commission expires: 5/1/1991