

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-19097-00-00

Well was completed on:
API NUMBER 6-25-1952

LEASE NAME Slinker Unit

WELL NUMBER 501

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 36 TWP. 4S RGE. 20 (E) (W)

COUNTY Phillips

Date Well Completed 6-25-1952

Plugging Commenced 5-11-1988

Plugging Completed 5-11-1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 29, 1988 (date)

by Mr. Dennis Hamel (KCC District Agent's Name).

Well was completed on:
Is ACO-1 filed? 6-25-1952 If not, is well log attached? Yes

Producing Formation Toronto Depth to Top 3081 Bottom 3088' T.D. 3313'

Lansing-Kansas City 3100 3266'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3081	3088	8-5/8"	205'	0
Lansing-Kansas City	Oil	3100	3266	5-1/2"	3313'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Ran in well & perforated the Anhydrite at 1445' w/4 SPF & below the Dakota at 860' w/3 SPF. Tied onto the 5-1/2" csg. and filled it to surf. w/225 sx 65/35 cmt. w/10% gel and 2% Econo. & 5 sx hulls. Tied onto the 8-5/8" csg. and filled the annulus to surf. w/8-5/8" csg. and filled the annulus to surface w/75 sx cmt. State Witness: Mr. Dennis Hamel
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Oil Services License No. _____

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Bryan Humphries *Carl M. Koyd*

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 88

Marsha B. Wilson
Notary Public

Commission Expires: 4-1-92

RECEIVED
STATE CORPORATION COMMISSION
5-22-88
AUG 12 1988
CONSERVATION DIVISION
Wichita, Kansas