

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R.-82-3-117

15-47-20218-00-06

API NUMBER 15-147-20,218

LEASE NAME Legg

WELL NUMBER #1

SPOT LOCATION 1350" FEL  
410' ENL

NE/4 SEC. 34 TWP. 4 SRGE. 20 (W)

COUNTY Phillips

Date Well Completed 9-27-76

Plugging Commenced 7-2-85

Plugging Completed 7-3-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS Box 4218, Logan, Ks. 67646

PHONE # (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Phillipsburg, Ks. -Dale Balthazor

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Ks. City Depth to top 3099 bottom 3296 T.D. 3404

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	oil & water	3099	3296	4 1/2"	3345"	none


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Perf. 4 shots at 1469 to 1470 Prod. 4 1/2" - Dumped 3 bbl. water before cementing. Fluid level was down 1720'. Pumped 50 sx. cement followed by 50 sx cement with 2 bags of hulls, followed by 15 sx gel. with 1 hull. Released plug. Pumped 100 sx cement. Shut in with 100# pressure. Surface - 8 5/8". Pumped 2 bbl. water with 1 hull, followed by 150 sx cement with 1 hull. Closed in 400# pressure 1:00 P.M.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ-Titan Services Company License No. NA  
Address Hays, Ks. 67601 Dist. # 33104

STATE OF Kansas COUNTY OF Phillips, ss.

I, Jim R. Baird, (~~operator~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird  
(Address) Box 428, Logan, Kansas



SUBSCRIBED AND SWORN TO before me this 18 day of Sept., 1985  
RECEIVED  
STATE CORPORATION COMMISSION  
Robert B. Hartman  
Notary Public

My Commission expires: 3/29/87

SEP 19 1985  
9-19-85  
CONSERVATION DIVISION  
Wichita Kansas