


15-147-00116-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 29 Twp. 4 Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner National Cooperative Refinery Association
Lease Name Becker Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 20, 19 54
Application for plugging filed March 23, 19 54
Application for plugging approved March 24, 19 54
Plugging commenced March 20, 19 54
Plugging completed March 21, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold Hollis
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 231', set plug with 1/2 sack of hulls, and dumped 15 sacks of cement.
Mudded hole to 40', set plug with 1/2 sack of hulls. Dumped 10 sacks cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer Drilling Company
Address 710 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. R. Sears
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 19 54

My commission expires June 30, 1954

C. Orville May
Notary Public.

24-7368-5 3-53-20M



C. Orville May
RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1954
CONSERVATION DIVISION
Wichita, Kansas

3-26-54

15-147-00116-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **National Cooperative Refinery Ass'n**
FARM **Becker** NO. **1**

SEC. **29** T. **4** R. **20W**
LOC. **SW SW SW**

TOTAL DEPTH **3660'**
COMM. **3/8/54** COMP. **3/20/54**
SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED

COUNTY **Phillips**
KANSAS

CASING
20 10
15 8
12 6
13 5 **231'**

ELEVATION **2073 K.B.**
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand & Clay	70
Shale	200
Shale & Shells	230
Shale	580
Shale & Sand	800
Sand	1070
Sand & Shale	1170
Sand	1380
Sand, Shale & Red Bed	1665
Anhydrite	1685
Shale Shells & Red Bed	2000
Shale & Shells	2255'
Shale & Lime Shells	2355
Shale, Shells & Lime Streaks	2545
Lime & Shale	2640
Shale & Lime & Streaks of Iron	2730
Shale & Lime	3272
Lime & Chert	3307
Lime, Chert & Shale	3333
Lime & Shale	3355
Lime, Shale & Chert	3366
Lime	3382
Lime & Shale	3408
Lime	3422
Lime & Shale	3462
Lime	3468
Shale	3519
Lime & Shale	3550
Cong. Shale & Cherty Lime	3578
Arbuckle	3620
Lime	3660

FORMATION TOPS (K.B. Meas.)

TOPEKA	3040
NEEDWIN	3235
TORONTO	3257
LANSING	3277
BASE K.C.	3468
ARBUCKLE	3575

STATE OF KANSAS
MAY 26 1954
CONSERVATION DIVISION
Wichita, Kansas

3-26-54

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By *P. P. Spunking*

STATE OF KANSAS
COUNTY OF SEDGWICK

SS:

PLUGGING
WELL SEC <u>29</u> T. <u>4</u> R. <u>20W</u>
BOOK PAGE <u>22</u> LINE <u>16</u>

Subscribed and sworn to before me, a notary public, in and for said County and State this 24th day of March, 1954.

Rose Lusny
Notary Public

My Commission expires February 13, 1956.