

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00950-06-00

API NUMBER 15-N/A

LEASE NAME Slinker Unit

WELL NUMBER 204

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

1980 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 25 TWP. 4S RGE. 20 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Phillips

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 8/15/60

Character of Well Oil

Plugging Commenced 11/3/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/3/94

The plugging proposal was approved on _____ (date)

by Carl Goodrow (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation LKC Depth to Top 3135 Bottom 3211 T.D. 3486

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
LKC	Oil	3135	3211	8 5/8"	157'	
				5 1/2"	3270'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perfed @ 920' & 1525' Pump 50 sks 60/40 POZ w/10% gel 1/4# sk Flocele w/ 100# hulls down ann. Shut press 350#. Hooked up to 5 1/2. Mixed & pumped 50 sks 60/40 POZ w/10% gel 1/4# sk Flocele, 150 # hulls. Followed by 12 sks gel, 125 sks 60/40 w/10% gel 1/4# Flocele & 250# hulls. Shut-in. Press to 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service License No. 5866

Address 505 W. Commercial, Logan KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 7th day of November, 1994

Sammy S Padilla
Notary Public

My Commission Expires: 8-21-96

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
Revised 05-88

NOV 10 1994

11-10-94
CONSERVATION DIVISION