

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-147-20270-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 26 TWP. 4S RGE. 20W E/W
 Location as in quarters or footage from lines:
 SW SE SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Baird Oil Company
 Lease Name States #1 Well No. _____
 Office Address Box 428 Logan, Kansas 67646
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 6-3-82
 Plugging completed 6-9-82
 Reason for abandonment of well or producing formation _____
 _____ Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3350'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	256'	none
				4-1/2"	3349'	2016'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed bottom plug to 3100', ran 50' of sand and 4 sacks cement. Shot casing @2010' and pulled a total of 50 joints of 4-1/2". Plugged well with 4 sacks hulls, 13 sacks gel, 70 sacks cement, 12 sacks gel, 8-5/8" plug, 70 sacks cement, 50/50 pos, 6% gel, 3% cc.

Plugging Complete.


RECEIVED
 STATE CORPORATION COMMISSION
 JUN 17 1982
 6-17-82

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1982



My Commission expires: _____

Irene Hoover
 Notary Public.