

API NUMBER 15-039-20003 -00-01

LEASE NAME Petracek

WELL NUMBER 2

 Ft. from S Section Line

SW SW NE Ft. from E Section Line

SEC. 9 TWP. 4 RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 2/12/67

Plugging Commenced 2-17-94

Plugging Completed 2-17-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well SWD EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-17-94 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	.0	218	8 5/8		None
	Casing	0	3764	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
TIH with 2" openended tubing to 3332'. Pump 175 sk. 60/40 -10% gelled. Circulated both 4 1/2 and 8 5/8 water and oil to surface. TOOH with 2" tbg. to 1025'. Circulate hole with 8 bbl. water Pump 75 sk. 60/40 -10% gel no hulls. Cement circulated to surface. Pull rest of tbg. Pump 50 sk. 60/40 10% gel 100# hulls down surface. Mix and pump 50 sk. down casing.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
 ROSEMARY SMITH
 My Appt. Exp. 5-1-1995

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 25 day of February, 19 94

Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 28 1994
 CONSERVATION DIVISION
 Wichita, Kansas