

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-30070-00-01

LEASE NAME Petracer

WELL NUMBER 1 in

3630 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 9 TWP. 04S RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 10/13/1966

Plugging Commenced 2-24-03

Plugging Completed 2-27-03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well injection EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/12/03 (date)

by Herb Dines (XCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Burlington Howards Topoka REAS + G Depth to Top 3309 Bottom 3648 T.O. 4035

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>Surface</u>	<u>Surface</u>	<u>302</u>	<u>8 5/8</u>		
	<u>Production</u>	<u>Surface</u>	<u>4639</u>	<u>5 1/2</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Rig up Allied-pump 100 SX 60/40 10% gel w/300# hulls via tbg. Pull tbg. to 1700' circ. cement to surface w/90 SX 60/40 10% pull tbg rig up to 250' pump 90 SX down - max psi 500# si @ 200 pump 15 SX 60/40 10% max psi 300# si @ 200# - plugging witnessed by Daryl Dipman XCC rep Hays

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address P.O. Box 723 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mark Leiter (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Mark Leiter


(Address) P.O. Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 4th day of March, 2003

Marion Sue Vance
Notary Public

My Commission Expires: 4-30-06

RECEIVED
03-07-03
MAR 07 2003



Form CP-1
Revised 05-88

KCC WICHITA

Bur