

15-147-00126-00-01

LEASE NAME Slinker Unit

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 101 W

3300' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 25 TWP. 4S RGE. 20 ~~W~~(W)

COUNTY Phillips

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Date Well Completed 5-6-68

Character of Well Input

Plugging Commenced 1-29-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-29-93

The plugging proposal was approved on January 29, 1993 (date)

by Mr. Denis Hamel of District #4 (KCC District Agent's Name).

Is ACO-1 filed? Well was completed on: 5-6-68 If not, is well log attached? yes

Producing Formation LKC Depth to Top 3133' Bottom 3444' T.O. 3550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	(Input Well)	3133	3444	10 3/4"	160'	
				7"	3483	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Perf. 1520-1521' and 885 to 886'. Hooked up to annulus and mixed 60/40 Poz. w/4% gel. Pumped 112 bbls. cmt. Hooked on 7" csg. & pumped 330 sx 60/40 Poz. w/4% gel. Pumped 12 bbls. and started adding hulls. Caught pressure after 25 bbls 250 psi Pressured to 1000 psi w/111 bbls cmt. State witness: Mr. Denis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Howco Cementing Company License No.                     

Address Wichita, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

VIC TUMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 93

[Signature] Notary Public

My Commission Expires: 8-21-96

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 12 1993  
 Form CP-4  
 Revised 05-88  
 CONSERVATION DIVISION  
 Wichita, Kansas