

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-19101-00-01

API NUMBER Drilled 1960

LEASE NAME Slinker Unit

WELL NUMBER 203W

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 25 TWP. 4S RGE. 20 ~~W~~ or (W)

COUNTY Phillips

Date Well Completed 1-20-60

Plugging Commenced 8-16-88

Plugging Completed 8-16-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS 110 S. Main, Wichita, Kansas 67202

PHONE# (316) 265-5624 OPERATORS LICENSE NO. 5447

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-14-88 (date)

by Mr. Dale F. Balthazor (KCC District Agent's Name).

Completed

Is ACO-1 filed? 1-20-60 If not, is well log attached? (Submitted with plugging application)

Producing Formation Toronto/LKC Depth to Top 3121'/3139' Bottom 3127'/3218' T.D. 3475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Oil-Water	3121	27'	8-5/8"	165'	None
Lansing-KC	Oil-Water	3139	3218'	5-1/2"	3281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Perforated the Anhydrite @ 1488' w/4 SPF and the Dakota @ 760' w/3 SPF. Pumped down 5-1/2" csg; 50 sx class "A" cement, 50 sx 60/40 Poz w/8% gel, 180 sx 60/40 Poz w/8% gel & 200# Hulls to surface. Pumped down csg Annulus; 120 sx 60/40 Poz w/8% gel & 200# Hulls to surface. (1/4# Flocele per sx slurry was also used in job).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services

Address Box 47, Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.


STATE OF Kansas COUNTY OF Sedgwick

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1988  
10-12-88  
CONSERVATION DIVISION  
Wichita, Kansas

Philip W. Pringle (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Philip W. Pringle

(Address) 110 S. Main, #800, Wichita, Kansas



WITNESSED AND SWORN TO before me this 12 day of October, 19 88

Alice Beery  
Notary Public

My Commission Expires: 4-5-89