

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22458-00-00

LEASE NAME Tribble

WELL NUMBER 9

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 20 (E) or (W)

COUNTY Roooks

Date Well (Completed) 9/20/04 <sup>KCC BEN</sup>

Plugging Commenced 9/20/04 <sup>10-19-04</sup>

Plugging Completed 9/20/04

OCT 18 2004  
RECEIVED

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St. Suite 500 Denver, CO

PHONE# (303) 585-9251 OPERATORS LICENSE NO. 33069

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/20/04 <sup>or 10-19-04</sup> (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Arbuckle Depth to Top 3436 Bottom 3728 T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	0	308	8 5/8"		none
	Producing Casing	0	3834	5 1/2"		none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s. Ran 2" Tubing to 2515' circulated to surface 180 sacks of 60/40 POS w/10% Gel cement with 500#'s of hulls in the first 50 sacks. Pulled tubing and pumped 80 sacks of cement down 5 1/2" casing @ 500#'s maximum pressure ISIP 300#'s. Pressure up on the 8 5/8" casing to 500#'s and it held.

Name of Plugging Contractor Alliance Well Service <sup>ed Cement Co.</sup> License No. 33346 9999 <sup>10-19-04</sup>

Address Ellis, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company

STATE OF Colorado COUNTY OF Denver, s.s.

Roland Nyp

above-described well, being first duly sworn on oath, says: That I have Employee of Operator or (Operator) knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STREET DENVER CO



TESTED AND SWORN TO before me this 14<sup>th</sup> day of October, 2004

Irene R. Nyp  
Notary Public

My Commission Expires: 9-30-08