

OCT 18 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Paul Bowman Oil Company
Address: 801 Codell Road, Codell, KS 67663
Phone: (785) 434-2633 Operator License #: 31008
Type of Well: Oil Docket #:
The plugging proposal was approved on: October 1, 2004
by: Dennis Hamel (KCC District Agent's Name)
Is ACO-1 filed? Yes No
Producing Formation(s): Arbuckle Depth to Top: 3801 Bottom: 3805 T.D. 3806

API Number: 15-065-00178-00-00
Lease Name: Buss C
Well Number: #1
Spot Location (QQQQ): SE-SE-NE-
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 13 Twp. 9 S. R. 22 East West
County: Graham
Date Well Completed: July 7, 1951
Plugging Commenced: October 4, 2004
Plugging Completed: October 4, 2004

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Arbuckle, oil/water, 259, 3802, 8 5/8", 259, none. Row 2: 5 1/2", 3802, none.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

2" tubing @ 2170' Spot 100 sx w/200# hulls, pull to 1085', spot 80 sx w/200# hulls, circulated cement to surface.
5 1/2" 60 sx @ 400# psi - shut in at 100#, 8 5/8" backside 25sx w/50# hulls

Name of Plugging Contractor: Allied Cementing Co Inc License #: 99996
Address: PO Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Paul Bowman, owner of Paul Bowman Oil Company
State of Kansas County, Rooks, ss.

Paul Bowman, Operator (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) Paul H Bowman
(Address) 801 Codell Road, Codell, KS 67663

SUBSCRIBED and SWORN TO before me this 14th day of October, 2004
Jackie J. Langholz My Commission Expires: 2-24-2005
Notary Public

Handwritten signature/initials

OCT 18 2004

RECEIVED

ALLIED CEMENTING CO., INC. 18908

Federal Tax I.D. [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>10-4-04</u>	SEC <u>13</u>	TWP. <u>9</u>	RANGE <u>22</u>	CALLED OUT <u>8:00Am</u>	ON LOCATION <u>10:30Am</u>	JOB START <u>10:45am</u>	JOB FINISH <u>1:00PM</u>
LEASE <u>Russ</u>	WELL# <u>C-1</u>	LOCATION <u>Bogue + RedLine Jct.</u>			COUNTY <u>GRAHAM</u>	STATE <u>KANSAS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>2 N 1 W 1/2 N 1/8 W INTO</u>					

CONTRACTOR Catool's (TERRY) OWNER _____

TYPE OF JOB Plug ABANDONED Well

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE 2" DEPTH 2170

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT (265 USED SK)

AMOUNT ORDERED 300 SK 60 10% Gel

500# Hull's

COMMON	<u>159</u>	@	<u>7⁸⁵</u>	<u>1248¹⁵</u>
POZMIX	<u>106</u>	@	<u>4¹⁰</u>	<u>434⁶⁰</u>
GEL	<u>20</u>	@	<u>11⁰⁰</u>	<u>220⁰⁰</u>
CHLORIDE		@		
ASC		@		
<u>HULLS</u>	<u>5</u>	@	<u>20⁰⁰</u>	<u>100⁰⁰</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>322</u>	@	<u>1²⁰</u>	<u>434⁷⁰</u>
MILEAGE	<u>51/51/115.5</u>	@		<u>1127⁰⁰</u>
TOTAL				<u>3564¹⁵</u>

EQUIPMENT

PUMP TRUCK CEMENTER Glen

366 HELPER Shane

BULK TRUCK

362 DRIVER GARY

BULK TRUCK

_____ DRIVER _____

REMARKS:

2" TUBING @ 2170' Spot 100 SK
w/ 200# Hull's. Pull up to
1085' & Spot 80 SK Cement w/
200 # Hull's - Cement Circ TO
Surface Hooked up to 5 1/2 CSG w/
Swage & Squeezed IN ANOTHER 60 SK
@ 400# max PSI, Shot IN @ 100#.
8 1/8 BACKSIDE 25 SK w/ 50 # Hull's
THANKS

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 525⁰⁰

EXTRA FOOTAGE @ _____

MILEAGE 70 @ 4⁰⁰ 280⁰⁰

MANIFOLD @ _____

TOTAL 805⁰⁰

CHARGE TO: PAUL BOWMAN Oil Co.

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____