

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10/4/2004 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 2860' Bottom: 2888' T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 053-20264-0000
Lease Name: Bultman
Well Number: 1
Spot Location (QQQQ): SW - SE - NW - SE
1640' Feet from North / South Section Line
1820' Feet from East / West Section Line
Sec. 16 Twp. 14 S. R. 10 East West
County: Ellsworth
Date Well Completed: 10/12/2004 *7-7-1972 KCC*
Plugging Commenced: 10/6/2004 *10-20-04*
Plugging Completed: 10/12/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	2980'	5-1/2"	2980'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10/6/04 - Sand perms to 2825', cap with 4 sx common cmt. Perforate w/2 holes ea. @ 1250', 900', 315'. Spot 35 sx 60/40 pozmix 4% gel @ 1275', 35 sx @ 872', cement 315' w/135 sx. Well did not circulate.
10/12/04 - Top csg. to surface w/38 sx 60/40 pozmix 4% gel. Cement stayed at surface. Virgil Clothier was on location.


Name of Plugging Contractor: Express Well Service License #: 6426
Address: P.O. Box 19, Victoria, KS 67671-0019
Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation
State of Sedgwick County, Kansas, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 18th day of October, 20 04

Glenna Lowe My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 20 2004
KCC WICHITA

bm