

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation

Address: 100 S. Main, Suite 200

Phone: (316) 262-3596 Operator License #: 9408

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/12/2004 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 2880' Bottom: 2888' T.D. Depth to Top: 2820' Bottom: 2830' T.D. Depth to Top: Bottom: T.D.

API Number: 15 - 053-20030-0000

Lease Name: St. Wencelaus Church

Well Number: 1

Spot Location (QQQQ): - NW - NW - SW

2310' Feet from North / South Section Line

330' Feet from East / West Section Line

Sec. 20 Twp. 14 S. R. 10 East West

County: Ellsworth

Date Well Completed: 10/12/2004

Plugging Commenced: 10/5/2004

Plugging Completed: 10/12/2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

10/5/04 - Well had been sanded to 1590'. Junk in hole. Spot 4 sx cmt. on sand. Perforate 2 holes ea. @ 1250', 850', 315'. Spot 35 sx 60/40 pozmix cmt @ 1275', 35 sx @ 872'. Pull tbg. to 315' and circulate to surface. Pull tbg., swedge to 4-1/2" and circulate 8-5/8" to surfce. Used 240 sx. 60/40 pozmix cmt. 2% gel. Rig down and move out. 10/12/04 - Top csg. with 37 sx 60/40 pozmix 4% gel. Cement stayed at surface. Virgil Clothier was on location

Name of Plugging Contractor: Express Well Service License #: 6426

Address: P.O. Box 19, Victoria, KS 67671-0019

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation

State of Sedgwick County, Kansas, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Gary Sharp

(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 18th day of October 20 04

Glenna E. Lowe Notary Public My Commission Expires:

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED OCT 20 2004 KCC WICHITA

Handwritten signature