



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas

11-25-68

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company, has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Kump Well No. 1

Location: SE-NE-SE Sec. 10 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3740' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Moore was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP. Pull
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

Very truly yours,

A. L. Nichols
 Conservation Division Agent