



15-039-20052-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
7-11-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co. Inc., has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Crandell Well No. 1

Location: NE-NW-NE Sec. 10 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3800 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burris was instructed to plug the well as follows:

217'--8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud. Pull DP to 1545' and displace 100 Sx. cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent