

State of Kansas



15-039-20295-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1974

CONSERVATION DIVISION
Wichita, Kansas

12-9-74

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this
date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Tilden Well No. 1

Location: CS/2-S/2-NE/4 Sec. 3 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3770' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent