



15-039-20188-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Morgan of Aspen Drilling Company has this date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Tomlinson Oil Company, Incorporated,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Tilden Well No. 1

Location: SE-NE-NE Sec. 3 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 4045' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

233'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1375' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent