



15-039-20204-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1970
CONSERVATION DIVISION
Wichita, Kansas
12-22-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Oller of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Shimmick Well No. 1

Location: SE-SE-SE Sec. 11 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3665' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

265'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent