



15-039-20108-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1969

CONSERVATION DIVISION
Wichita, Kansas

8-21-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Morgan of Champlin Petr. Co. has this
 date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Co.

Complete Address: Box 308 Ellinwood, Kansas

Lease Name: Shimmick Well No. 1

Location: G SW SE Sec. 14 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3725' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Morgan was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1300' and displace
100 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Conservation Division Agent