

State of Kansas



15-039-30004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1965

CONSERVATION DIVISION  
Wichita, Kansas  
8-10-65

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Lowery of Burch Exploration, Ltd., has this

date requested permission to plug the following described well:

National Assoc. Petroleum,

Mr. Lowery guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: 5th Floor Ritz Building, Tulsa, Oklahoma.

Lease Name: Petracek Well No. 1

Location: NW-NW-NW Sec. 11 Twp. 4 Rge. (E)(W) 27

County Decatur Total Depth 3810 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lowery was instructed to plug the well as follows:

247' -- 8 5/8" Surface pipe, cement circulated with 225 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	240' with $\frac{1}{4}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

Conservation Division Agent