



15-147-19094-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Brenthenger of Midwestern Supply Co. Inc. has this date requested permission to plug the following described well:

Mr. Midwestern Supply Coguarantees payment of the plugging fee.

Operator's full Name: Wilkinson Drilling, Inc. & Midwestern Supply Co., Inc.

Complete Address: 710 Union Nat'l. Bldg., Wichita, Kansas 67202

Lease Name: Lutz Well No. # 1

Location: NE SE SW Sec. 35 Twp. 4 Rge. 20 (E)(W) W

County: Phillips Total Depth 3424 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pulley was instructed to plug the well as follows:

8 5/8" 246' Cwc. 5 1/2" 3424' Perf. 3356'.

Sanded hole back to 3320' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 5 sax hulls, 20 sax mud, & 120 sax

cement with Allied Cementing Company's pump truck, cementing from

450' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

JUL 3 1969

CONSERVATION DIVISION
Wichita, Kansas

Don Truman 7-3-69
Conservation Division Agent