

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03310-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 14-16S-12W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HOFFMAN A Well #: 2  
County: BARTON Total Vertical Depth: 3377 feet

Operator License No.: 6296  
Op Name: HOLT, IVAN LEROY  
Address: PO BOX 401 NORTH VAN HOUTEN ST  
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3376 75 SX CMT  
SURF Size: 8.625 feet: 259 150 SX CMT

\$109<sup>75</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2004 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-1724

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/21/2004 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Had bridge and holes at 700'.  
Worked tubing to 1250'.  
Pumped 165 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
Pulled to 625'.  
Pumped 60 sxs cement - hole circulated.  
POOH.  
Tied onto casing and pumped 30 sxs cement - circulated up backside.  
Shut in backside.  
Pumped 20 sxs cement.  
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED  
OCT 14 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

120

Signed Case Morris  
(TECHNICIAN)

INVOICE

DATE 10-14-04  
INV. NO. 2005060653

Form CP-2/3

OCT 12 2004

TRANS ERA PETROLEUM

#2

HOFFMAN

14-16-12W  
NE NW SW

Contr. TRANS ERA PETROLEUM

BARTON

County

E. 1922

Comm.

Comp.

4-24-53

IP

25 BOPD

Tops	Depth	Datum
HEEB	3006	-1084
BR LM	3097	-1175
KC	3116	-1194
ARB	3375	-1495
	-1453	
TD	3377	-1455

Casing  
5" 3376½

DP, 25 BOPD

KRAFT-PRUSA POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Vertical stamp or text on the left margin, partially illegible.