

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22034-00-01
Spot: N2SWNE Sec/Twnshp/Rge: 36-17S-13W
3630 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HICKEL OWWO Well #: 1
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 6296
Op Name: HOLT, IVAN LEROY
Address: PO BOX 401 NORTH VAN HOUTEN ST
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3404 150 SX CMT
SURF Size: 8.625 feet: 250 180 SX CMT # 110⁶³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (784) 483-1724

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2004 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Cut holes at 1500' - 720' - 250'.
Ran tubing to 1200'.
Pumped 165 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled to 600'.
Circulated with 40 sxs cement.
POOH.
Tied onto casing and pumped 50 sxs cement.
Cement circulated up backside - shut in.
Pumped 10 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3339	3341		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10

Signed *Case Morris*
(TECHNICIAN)

INVOICED

10-14-04
2005060653

OCT 12 2004

INAOICED

L.D. DRILLING, INC.

RT. 1, BOX 183-B
GREAT BEND, KS. 67530

#1 HICKEL 'OWWO'


36-17-13W
C N/2 SW NE

CONTR DUKE DRILLING

CITY BARTON

GEOLOGICAL BRUCE REED

FIELD REDWING WEST



ELV 1823 KB SPD 9/4/85 CARD ISSUED 10/17/85 IP P 15 BO & 30 BWPD
1818 GL DRLG COMP 9/5/85 ARB 3339-3341
API 15-009-22,034-A

	Tops	Depth/Datum
SMP		
ANH	713	+1110
B/ANH	736	+1087
HOW	2666	- 843
TOP	2706	- 883
QH	2907	-1084
HEEB	2989	-1166
TOR	3008	-1185
DOUG	3018	-1195
BR LM	3083	-1260
LANS	3097	-1274
BKC	3317	-1494
ARB	3338	-1515
ORTD	3349	-1526
DDTD	3404	-1581

OLD INFO: OPERATOR WAS ICER ADDIS, #1 HICKEL, SPD 8/18/80, SET 8 5/8 " 250 / 180 SX, COMP AS D & A / ARB 8/23/80 (CARD ISSUED 9/4/80), CONTR: L.D. DRILLING COMPANY, INC., GEOLOGICAL: BRUCE REED

DST (1) 3314-3344 (ARB) / 30-30-30-30, REC 90' M, W/OIL SPTS & W / FREE OIL IN TOOL, SIP 992-981#, FP 32-43# / 53-64#

DST (2) 3342-3349 (ARB) / 30-30-30-30, REC 330' WTR, SIP 992-971#, FP 43-96# / 117-160#

NOTE: CORRECTION 7/16/81 - ORIGINALLY FIRST REPORTED AS C W/2 SW NE

NEW INFO: FR 8/30/85, RE-ENTERED 9/4/85, WSH DWN TO ORTD, DD 3404 TD, SET 5 1/2 " 3403, MICT - CO, PF (ARB) 3339-41, W / 2 SPF, AC 500G (28% NE), SWB DWN, SO, SET 2 3/8 " TBG AT 3394, POP, P 15 BO & 30 BWPD, 9/12/85