

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01822-00-00
Spot: SESWSW Sec/Twnshp/Rge: 17-12S-15W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HOLLAND Well #: 1
County: RUSSELL Total Vertical Depth: 3266 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

PROD Size: 4.5 feet: 3262 200 SX CMT
SURF Size: 8.625 feet: 900 400 SX CMT

\$106¹⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MIKE MCGLOCKLIN Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-9800

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2004 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 900' and 450'.
Ran tubing to 1680'.
Pumped 325 sxs 60/40 pozmix - 10% gel cement with 700# hulls.
Had circulation up backside almost the entire time.
Cement did not circulate inside casing.
Let set over-night.
09-17-2004 - Ran in with tubing. Stacked out at 680'.
Circulated with 50 sxs cement with 300# hulls.
POOH.
Pressured casing to 200# P.S.I.
Pressured backside to 400# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3262	3266		
3003	3009		
2488	2492		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10P

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 10-14-04

INV. NO. 2005060656

OCT 12 2004

17-12-15W
SE SW SW

SHIELDS OIL PROD

#1 HOLLAND

Contr. SHIELDS DRLG


RUSSELL County

E 1850^{RA} Comm.

Comp. 11-2-56 IP 25 BOPD

Tops	Depth	Datum	Casing
			8" 900
TOP	2705	-855	4" 3262
HEEB	2924	-1074	DST 2871-2905/1 HR, 480' G, 145' HO & GC M, BHP 570#
TOR	2943	-1093	DST 2930-60/1 HR, 420' G, 125' O & GCM BHP 380#
LANS	2978	-1128	DST 2979-90/1 HR, 80' G & GCM, 247' O & GC SW, BHP 220#
			DST 3004-25/1 HR, 2,050 G, 115' MLY O, 60' FEE O, BHP 340#
GORH SAND	3260	-1110	DST 3052-80/1 HR, 250' G, 70' O & GCM, FAIRPORT POOL 300' & GC SW, BHP 600#
			2: 00 TO
TD	3266	-1416	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



NOICE