

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20222-00-01
Spot: N2NESE Sec/Twnshp/Rge: 19-4S-18W
2310 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: SUTLEY B Well Number: 1
County: PHILLIPS Total Vertical Depth: 3330 feet

Operator License No.: 5242 Conductor Pipe: Size feet:
Operator Name: PETROLEUM MANAGEMENT, INC Surface Casing: Size 8.62 feet: 215 170 SX CMT
Address: 14201 EAST CENTRAL Production: Size 4.5 feet: 3329 175 SX CMT 108.23
WICHITA, KS 67230 Liner: Size feet:

Well Type: EOR UIC Docket No: E26963.1 Date/Time to Plug: 10/27/2000 2:15 PM
Plug Co. License No.: 5242 Plug Co. Name: PETROLEUM MANAGEMENT, INC.

Proposal Rcvd. from: LARRY WALLERT Company: PETROLEUM MANAGEMENT, INC. Phone: (316) 733-5600

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel and hulls.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/27/2000 2:45 PM KCC Agent: HUBERT DEINES

Actual Plugging Report:

8 5/8" to 212' w/170 sxs. 4 1/2" to 3329' w/175 sxs.
Squeezed 734' - 1540' w/250 sxs.
Tied onto annulus and had instant 500# pressure.
Tied onto production casing and pumped 170 sxs cement with hulls.
Max. P.S.I. 1100#. S.I.P. 800#.

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 2000
11-03-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 11/6/00

INV. NO. 2001060937

Form CP-2/3

OCT 31 2000

PETROLEUM MANAGEMENT, INC.
 400 N. WOODLAWN, SUITE 201 #1 SUTLEY "B" 19-4-18W
 WICHITA, KS. APPX N/2 NE SE
 CONTR RED TIGER DRILG. CO. CTY PHILLIPS

GEOL _____ FIELD STONEMAN EXT (1/8sw)

E 1884 KB CM 10/27/76 ^{CARD} ISSUED 2/10/77 IP P 10 BOPD + 56% W
 LKC 3130-34, 3167-71
 & 3189-93

	+	+	+
	+	+	+
	+	+	+

API 15-147-20,222

SMP	TOPS	DEPTH	DATUM
B ANH		1451	+ 433
OREAD		3006	-1122
HEER		3052	-1168
LANS		3092	-1208
BKC		3319	-1435
RTD		3330	-1446

8-5/8" 212/170sx, 4 1/2" 3329/175sx
 NO LOG
 DST (1) 3105-3180/45-45-45-45, 90' M W/
 SP 0, SIP 888-805# FP 74-102# 102-
 121#
 MICT - PF 3130-34, AC 1250, FP 3167-71
 & 3189-93, AC 2250, REC LD, SWB 3 BFPH,
 25% OIL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS