

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20059-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 20-4S-18W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: JACKSON-ELSIE Well Number: 10
County: PHILLIPS Total Vertical Depth: 3406 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

Production Casing Size: 4.5 feet: 3385 150 SX CMT **\$110.70**
Surface Casing Size: feet: 0
Surface Casing Size: 8.625 feet: 208 160 SX CMT

Well Type: EOR UIC Docket No: E26093.2 Date/Time to Plug: 05/12/2003 9:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: PAUL NIXON Company: NIXON, R.P. OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel - 600# hulls.
D.V. at 1745' set with 665 sxs.
Packer left in the hole at 2860'.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/12/2003 12:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2800'.
Mixed and circulated cement with 140 sxs cement and 400# hulls.
POOH and topped with 20 sxs cement.
S.I.P. 500#.
Annulus full of cement.

RECEIVED
MAY 30 2003
05-30-2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

J Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-30-03
INVOICE NO. 2003061592

MAY 27 2003

INDEX

T. W. JACKSON #10 JACKSON-ELSIE 20-4-18W
 PHILLIPSBURG, KS. NW NW NE
 Contr. RED TIGER DRLG. CO. Cty. PHILLIPS
 Geol. DICK GRANT Pool STONEMAN
 E. 1936 KB Cm. 12/16/69 Cp. 6/26/69 IPPMP 23 BOPD + WIR/
 LKC 3148-3247
 API 15-147-20,059

LOG Tops	Depth	Datum
ANH	1468	+ 468
TOP	2903	- 967
HEEB	3105	-1169
TOR	3128	-1192
LANS	3146	-1210
BKC	3372	-1436
TD	3406	-1470

Csg. 8" 200 4 1/2" 3385
 CO PF 1/3245, 1/3247, 1/3224,
 1/3209, 1/3189, 1/3149, A 250
 SWB LD & SWB GSO, A 5000, NO
 TST, PF 16/3243-47, 16/3207-11
 24/3186-92, 16/3148-52 (LKC)
 SWB DN & SWB GSO/4 HRS, POP
 NO DSTS
 NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS