

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰¹ 15-147-20033-00-06
Spot: SENESE Sec/Twnshp/Rge: 20-4S-18W
1650 feet from S Section Line, 1140 feet from E Section Line
Lease/Unit Name: STONEMAN Well Number: 11
County: PHILLIPS Total Vertical Depth: 3334 feet

Operator License No.: 5242 Conductor Pipe: Size feet:
Operator Name: PETROLEUM MANAGEMENT, INC Surface Casing: Size feet: 206
Address: 14201 EAST CENTRAL Production: Size 4.5 feet: 3333 225 SX CMT 108.36
WICHITA, KS 67230 10/19 Liner: Size feet:

Well Type: EOR UIC Docket No: E12730.5 Date/Time to Plug: 10/19/2000 12:00 AM

Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC

Proposal Rcvd. from: LARRY WALLERT Company: PETROLEUM MANAGEMENT, INC. Phone: (785) 735-4495

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel and hulls.
Plug through tubing.

Plugging Proposal Received By: HUBERT DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 10/19/2000 11:15 AM

KCC Agent: HUBERT DEINES

Actual Plugging Report:

8 5/8" set to 203' w/160 sxs. 4 1/2" set to 3333' w/225 sxs.
Squeezed holes from 685' - 1708' - three times with total of 510 sxs cement.
Top perf at 3032' and bottom perf at 3289'.
Ran tubing to 1900' and pumped 50 sxs cement with hulls.
Pulled tubing to 950' and pumped 50 sxs with cement to surface.
Pulled tubing. Tied onto production casing and pumped 10 sxs cement.
Pressured to 700#. Tied onto annulus and pumped 40 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
STATE CORPORATION COMMISSION


NOV 3 2000
11-03-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION READS AS FOLLOWS: 150' W.OF SENESE 20-04-18W.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 11/6/00

INV. NO. 2001060937

Form CP-2/3

OCT 31 2000

