

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20199-00-00  
Spot: CW2SWNW Sec/Twnshp/Rge: 31-4S-26W  
3300 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: ACKERMANN Well Number: 1  
County: DECATUR Total Vertical Depth: 3682 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N. MARKET, STE 1130  
WICHITA, KS 67202

Conductor Pipe: Size feet: 3 1/2  
Surface Casing: Size 10.75 feet: 233 w/160 sxs cmt  
Production: Size 4.5 feet: 3681 w/250 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/18/2002 1:00 PM  
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.  
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Plugging Method: Ordered out 165 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Job ticket AH prior squeeze.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/18/2002 3:30 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Ran tubing and tagged cement at 2190'.  
Pulled one joint.  
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls. Circulated cement.  
PTOH. Squeezed with 15 sxs.  
Max. P.S.I. 1000#. S.I.P. 500#.  
Hooked up to backside.  
Allied pumped 50 sxs 60/40 pozmix - 10% gel with 100# hulls.  
Max. P.S.I. 100#. S.I.P. 100#.  
Note: Bottom plugged. Top cement 2190'.

RECEIVED  
JUN 21 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

**INVOICED**

Form CP-2/3

DATE 6-24-02

NO 2002061992

JUN 19 2002

R. W. SHIELDS &  
 E. K. EDMISTON #1 ACKERMANN 31-4-26W  
 WICHITA, KANSAS W/2 SW NW  
 CONTR JOHN O. FARMER, INC. CTY DECATUR

GEOL BILL IVERSEN FIELD JENNINGS EXT  
 E 2578 KB CM 11/23/70 CARD ISSUED 3/25/71 IP 3492-96, 3517-20,  
 3548-50, 3563-66 &  
 3592-95


API 15-039-20,199

LOG	TOPS	DEPTH	DATUM	
				10 3/4" 233/160sx; 4 1/2" 3681/250sx
ANHY		2083	+ 495	DST(1) 3150-70/11, 15'M, BHP 496-766//30", FP 18-45#
TARK		3166	- 588	DST(2) 3484-3530/1145", 280'GIP, 200'HOCM, BHP 712-559//30", FP 45-144#
HOW		3257	- 679	DST(3) 3530-75/1115", 390'GIP, 90'GSY OIL, 180'o & GCM, BHP 685//30"-695//60", FP 36-159#
HEEB		3452	- 874	DST(4) 3605-3682/45", 20'M, BHP 775-586//30", FP 54-81#
TOR		3476	- 898	
LKC		3491	- 913	
BKC		3680	-1102	MICT, PF 1/3593, 1/3564, 1/3594 A2000 RE-PF 4/3548-50, 12/3563-66, 12/3592-95 SWB 1800/1ST HR SWB 15
LTD		3681	-1103	BO/2NDHR & TR AC WTR SD/12 FU 1800'OIL, SWB 1280
RTD		3682	-1104	700'OB, N/W, BP 3528, 1/3518, 1/3493, A1500, RE-PF OIL/12HRS SWB 14BOPH, BP 3310, PF(HOW)12/3258-62
	12/3517-20	16/3492-96	FU 1800	A250 MA, SWB DWN A1000(.28%AC) SWB DWN SHORT 10BL SWB 10BOPH, SWB 3 1/2 BW LAST HR, SI/12HRS FU 900'EL 90% WTR, PULL PLUG, CO & POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

11/23/70  
 3/25/71  
 15-039-20,199