

TO:

API number: 15- 147-20,054-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

NE NW NE /4 SEC: 20 - 04 - 18 W
4950 Feet from S (N/S) Line
1650 Feet from E (E/W) Line

Operator License# 5252

LEASE: Elsie-Jackson WELL # 9

Operator: R. P. Nixon Operations, Inc.

County: PHILLIPS 110-18

Address: 207 West 12th Street
Hays, Kansas
67601

Well total Depth 3390 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8" inch @ 205 feet

Aband. Oil Well Gas Well Input Well SWD: D & A:

Pluggin contractor: Jay-Lan Corp License#: 5128

Address: 207 West 12th, Hays, Ks

Company to plug at: Hour: 01:00 pm Day: 12 Month: May Year: 1997

Plugging proposal received from: Paul Nixon

Company: Jay-Lan Corp. Phone: _____

Were:

4 1/2" casing set at 3385' with 150 sx. Perf well @ 900' and 1500'. Run tubing to 1600'. Pump 60/40 poz, 10% and hulls until cement circulates. Pull tubing. Tie onto 4 1/2" casing and pump 60/40 poz, 10% gel and hulls until develop pressure. Tie onto 8 5/8" X 4 1/2" annulus and fill with 60/40 poz, 10% gel until pressure develops.

Plugging proposal recived by: Herb Deines

Pluggings operations attended by agent? All [], Part [X], None []

Completed Hour: 02:10 pm Day: 12 Month: May Year: 1997

Actual plugging report:

Perfed well at 900' and 1500'. Ran tubing to 1600'. Pumped 160 sx 60/40 poz, 10% gel, 400# hulls down tubing, Cement circulated. Pulled tubing. Tied onto 4 1/2" casing and squeezed with 50 sx 60/40 poz, 10% gel and 100# hulls. Maximum pressure 400 psi. Shut in pressure 200 psi. Tied onto 8 5/8" X 4 1/2" annulus and pumped 0 sx cement, pressured to 400 psi.

Remarks: Elevation: 1940 GL, Anhydrite top: feet Anhy. plug Y

Dakota plug: Y Bottom plug in place: Y

Plugged through drill pipe: T

Arbuckle top: Cemented by: Allied

I did [X] did NOT [] observe the plugging.

INVOICED

DATE 6-24-97

INV. NO. 48400

Bruce Basye

Bruce Basye (agent)

RECEIVED
MAY 21 2 12 PM '97
KANSAS CORP COM
05-24-1997