

4-071102

7-14

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-147-20,558-00-00

NW NW SW /4 SEC. 18, 04 S, 18 W  
2310 feet from S section line  
4950 feet from E section line

Operator license# 5011

Lease Shaw well # 1

Operator: Viking Resources, Inc.

County Phillips

111.47

Address: 105 S. Broadway - #1040  
Wichita, Kansas 67202  
Shawn Devlin

Well total depth 3430 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 14 Month: July Year: 94

Plugging proposal received from: Keith Vanpelt

Company: Murfin Drilling Company Phone: 316-262-2502

Were: 8 5/8" - 212' cwc. w/140 sxs. 60/40 pozmix - 3% c.c. - 2% gel.  
By Allied Cement. K.C. well - Elv. 1967' - Anhy. 1525' - No circulation  
problems - Mud condition 58 vis. - 9.2 wt. - 8 water loss - 1100 ppm cl.  
at T.D. Proposal 190 sxs. 60/40 pozmix - 6% gel - 1 sx. flocele.  
Circulate hole - 42-45 vis.mud. Spot and displace all cement through  
drill stem - heavy mud between all plugs. 25 sxs. @ 1530' - 100 sxs. with  
1 sx. flocele @ 900' - 40 sxs. @ 260' - 10 sxs. @ 40' - 15 sxs. in rathole.  
(circulate)

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 11:45A.M., Day: 14, Month: July, Year: 94

Actual plugging report: Murfin ordered 190 sxs. 60/40 poazmix - 6% gel -  
1 sx. flocele. Circulated hole - spotted and displaced all cement  
through drill pipe. Heavy mud between all plugs.  
1st. plug at 1530' w/25 sxs. cement.  
2nd. plug at 900' w/100 sxs. cement w/1 sx. flocele.  
3rd. plug at 260' w/40 sxs. cement.  
4th. plug at 40' w/10 sxs. cement.  
15 sxs. in rathole (circulated)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1994  
07-19-1994  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cemented by: Allied Cement.  
Condition of casing(in hole): GOOD     BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation: 1967 GL    

I did     / did not X observe the plugging.

*Marion J. Schmidt*  
(agent)

HO

Form CP-2/3

INVOICED

DATE JUL 28 1994

INV. NO. 40914 SEP 28 1994