

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21631-00-00  
Spot: NWNENWNE Sec/Twnshp/Rge: 14-35S-12W  
378 feet from N Section Line, 1927 feet from E Section Line  
Lease Name: GOTTSCH-PETERMANN Well #: 3  
County: BARBER Total Vertical Depth: 4925 feet

Operator License No.: 6006  
Op Name: MOLZ OIL COMPANY  
Address: 19159 S.W. CLAIRMONT  
KIOWA, KS 67070

CIBP Size: feet: 4700 WITH 2 SX CMT  
PROD Size: 5.5 feet: 4920  
SURF Size: 8.625 feet: 467 WITH 300 SX CMT

*\$160<sup>06</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2004 10:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/30/2004 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4700 & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID CASING DOWN & SPOT PLUGS THROUGH 2 7/8" TUBING. 1ST PLUG AT 650' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4840	4852		

RECEIVED  
OCT 13 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3300' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*Stephen J. Gartin*  
(TECHNICIAN)

INVOICED

DATE 10-13-04  
INV. NO. 2005060604

Form CH 2/8