

4- 090539

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-2

API number: 15-137-20,398-00-00

NE SE SE /4 SEC. 04, 04 S, 23 W
990 feet from S section line
330 feet from E section line

Operator license# 5050

Lease: Sproul Well # 1

Operator: Hummon Corporation

County: Norton 127.08

Address: 200 W. Douglas - #1020
Wichita, Kansas 67202

Well total depth 3910 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 356 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Nebraska Drilling Company License# 31730

Address: _____

Company to plug at: Hour: P.M. Day: 28 Month: November Year: 1995

Plugging proposal received from: Bob Horinek

Company: Nebraska Drilling Company Phone: -

Were: Order 215 sxs 60/40 posmix - 6% gel.
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher
Plugging operations attended by agent? All[], Part[], None[X]

RECEIVED
STATE CORPORATION COMMISSION
12-13-95
DEC 13 1995

Completed: Hour: 11:45 P.M., Day: 2, Month: December, Year: 1995

Actual plugging report:
1st. Plug at 3910' w/20 sxs cement.
2nd. Plug at 2095' w/20 sxs cement.
3rd. Plug at 1290' w/100 sxs cement.
4th. Plug at 405' w/40 sxs cement.
5th. Plug at 40' w/10 sxs cement.
15 sxs rathole. 10 sxs mousehole.
Arbuckle - yes - Anhydrite 2084'

Remarks: Allied Cementing
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES 2084 NO _____
Bottom plug(in place): YES ✓, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____ Elevation: 2448 GL

I did observe the plugging.

INVOICED

Ed Schumacher
(agent)

Form CP-2/3

DATE 1-5-96

INV. NO. 44394

12-2