

6010273

15-137-20349-00-00 R

API NUMBER 15- 137-20,349

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 4, T. 4 S, R. 23 W/E

4950 feet from N section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name Reich Well # 1

Operator: Allen Drilling Co.

County Norton 128.83

Name & Address Box 1389

Well Total Depth 3964 feet

Great Bend, Ks. 67530

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Allen Drilling License Number 5418

Address Same as above

Company to plug at: Hour: AM Day: 13 Month: December Year: 19 84

Plugging proposal received from Craig Christhoper

(company name) Allen Drilling (phone)

were: Order 185 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flow seal, 1 sk hulls and
8 5/8" plug. Spot with drill pipe with no less than 35 vis. mud between all plugs,
with good circulation and no fluid loss.

Elevation = 2471 Anhydrite = 2098-2125 Arbuckle = No Dakota = 1450

Dakota 1450 Plugging Proposal Received by Del F. Batchelor (TECHNICIAN)
10 21-1320

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 2:45 PM Day: 13 Month: December Year: 19 84

ACTUAL PLUGGING REPORT Circulate at 2110 for 30 minutes

25 sks @ 2110

100 sks @ 1320 w/1 sk flow-seal

40 sks @ 400

10 sks @ 40 on solid bridge

10 sks in Rat Hole

Remarks: Cemented by Halliburton

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 1-7-85

TIME 6310

Signed Del F. Batchelor (TECHNICIAN)