

6 030890

API NUMBER 15- 137-20,170 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C NE NW, SEC. 4, T 4 S, R 25 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Brooks Well # 1

Operator: Thunderbird Drilling Inc.  
Name & Address: Box 97  
Ellinwood, Kansas 67526

County Norton 132.41  
Well Total Depth 4074 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 290'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Eng. Inc. License Number 5111  
Address Great Bend, Kansas 67530

Company to plug at: Hour: AM Day: 4 Month: June Year: 19 87

Plugging proposal received from Deacon

(company name) Rockhold Eng. Inc. (phone) \_\_\_\_\_

were: 8 5/8 set at 290' w/250 sks 4 1/2 set at 3710 w/100 sks PBTB 3587'.

Perf. 3574-77'. Order sand and com cmt. Pull pipe.

Order 200 sks Atl. 65/35 Poz 10% Gel 2% Dicel

Allied Cmt. Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 AM Day: 4 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3500' w/4 sks com. cmt. on sand w/bailer.

Shots at 3000' 2100' 1700' 1400' 1200' 1000'. Recovered 1000' of Csg.

Mix and pump down 8 5/8 200 sks cmt blend w/5 sks Hulls. Max Psi. 400# close in  
150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1987 7-16-87

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED  
Please observe this plugging.

DATE 7-21-87

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

INV. NO. 17543 6-4 JUL 30 1987