

6030390

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,697-00-00

NESW 1/4 SEC. 29, T. 4 S, R. 26 W

3630 feet from N/S section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Hardesty Well # 1

Operator: Murfin Drly. Co.

County Decatur 129.19

Name & Address 250. N Water Ste. 300

Well Total Depth 3975 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 197 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drly. Co. License Number 6033

Address above.

Company to plug at: Hour: AM Day: 6 Month: 3 Year: 19 85

Plugging proposal received from Stan.

(company name) Murfin Drly. Co. (phone) _____

were: 8 5/8 set @ 197 w/ 160 cc cement - 4 1/2 set @ 3971 w/ 175 cc cement +

Recovered 1105' of 4 1/2 casing shot @ 1200' was solid - stuck tight.

Ordered 1 70 cc 50 sp of 6 3/4 gel 3 1/2 cc. 40 cc gel - 4 cc hulls. 8 5/8 wiper

plug. Topper @ 3540' Halliburton Cement Co., Overlin, Ka.

Murfin and Harman's water trucks.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:AM Day: 6 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Bottom plug 4 cc. Com. Cem. Sand to 3300'. 4 cc Com. Cem.

Top Plug - Pump down 8 5/8 - 3 hulls - 25 cc gel - 100 cc Com. mix. 15 cc

gel - 1 cc hulls - 8 5/8 wiper plug. 70 cc Com. mix. Max. 200"

held 200" shut in R 200". Plugging complete.

MAR 28 1985

3-28-85

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (did/did not) observe this plugging.

Signed Carl Goodnow 3-27-85
(TECHNICIAN) 11

DATE 4-3-85

INV. NO. 7514