

2-1
179 R
4- 060294

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-039-20,881-00-00
NE NW SE /4 SEC. 19, 04 S, 26 W
2310 feet from S section line
1650 feet from E section line

Operator license# 30870 Lease Tacha well # 1

Operator: Reynolds-Rexwinkle Oil, Inc. County Decatur

Address: 212 N. Market #402 Well total depth 3660 feet 118.95
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 301 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allen Drilling License# 5418

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 5:00P.M. Day: 1 Month: February Year: 92

Plugging proposal received from: Mike Kern

Company: Allen Drilling Company Phone:

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00P.M., Day: 1, Month: February, Year: 92

Actual plugging report:
1st. plug at 2050' with 25 sxs. - Anhydrite 2038' - 2076'
2nd. plug at 1290' with 100 sxs. - Dakota 987' - 1287'.
3rd. plug at 350' with 40 sxs. - Surface pipe 301'.
4th. plug at 40' with 10 sxs.
Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
MAR - 3 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2462 GL

I did[] / did not[X] observe the plugging.

DATE MAR 10 1992

WV. NO. 34716
2-1

Herb S.

Herb Deines

(agent)
Form CP-2/3