

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20036-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas
11-6-69

Operator's Full Name Lario Oil and Gas Company,

Complete Address 301 South Market, Wichita, Kansas.

Lease Name Arthur L. Henry Well No. 1

Location 100' North of CE/2-NE-NE Sec. 10 Twp. 4 Rge. (E) (W) 23

County Norton Total Depth 3678'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas License No. _____

Operation Completed: Hour 2:30 PM Day 3 Month 11 Year 1969

The above well was plugged as follows:

273'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru
DP from 1125' to 800'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from 325'
to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 11/6/69
INV. NO. 781-W