

KANSAS

Form CP-3
Rev. 6-4-68

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20093-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

1-7-71
RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. Ainsworth,

Complete Address 310 Brown Building, Wichita, Kansas.

Lease Name Harting Well No. 5

Location NW-NW-SW Sec. 2 Twp. 4 Rge. (E) (W) 23

County Norton Total Depth 3706'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 2:00 PM Day 28 Month 12 Year 1970

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 175 Sx.
3696'--5 1/2" Production casing cemented on bottom with 75 Sx. (Open hole completion).

Sanded well back to 3675' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with initially 5 sacks hulls and 13 sacks gel and followed with 100
Sx. cement from 1100' to 775' then 14 sacks gel from 775' to 225' and followed with 25
Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx.
cement from 30' to bottom of cellar. Maximum pump-in pressure-350#. FSIP-150#.
(Mudding and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 1/7/71

INV. NO. 3-176-4