

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20030-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1969

CONSERVATION DIVISION  
Wichita, Kansas

8-14-69

Operator's Full Name A. Ainsworth,

Complete Address 310 Brown Building, Wichita, Kansas.

Lease Name Browne Well No. 1

Location SW-NE-SW Sec. 2 Twp. 4 Rge. (E) (W) 23

County Norton Total Depth 3744'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor B & B Drilling, Incorporated.

Address 207 Petroleum Bldg., Wichita, Ks. License No.       

Operation Completed: Hour 6:00 PM Day 7 Month 8 Year 1969

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru  
DP from 1175' to 850'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/14/69

INV. NO. 293W

Signed: W. B. Nichols  
Well Plugging Supervisor