

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20073-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1968
CONSERVATION DIVISION
Wichita, Kansas
11-25-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Kump Well No. 1

Location SE-NE-SE Sec. 10 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C & G Drilling Company,

Address: 1107 Union National Bank Bldg., Wichita, Ks. License No.

Operation Completed: Hour 6:30 AM Day 20 Month 11 Year 1968

The Above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru
DP from 1350' to 1025'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215' to
155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/26/68

INV. NO. 8884-W

Signed: *M. G. Nichols*
Well Plugging Supervisor