

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20052-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

7-11-68
RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Crandell Well No. 1

Location NE-NW-NE Sec. 10 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3800

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 10:00 AM Day 4 Month 7 Year 1968

The Above well was plugged as follows:

217'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud. Pulled DP to 1545' and displaced 100 Sx. cement thru

DP from 1545' to 1220'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from

245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 7/12/68
INV. NO. 8079-W