

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00134-06-00

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1961

CONSERVATION DIVISION
Wichita, Kansas

11-14-61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Decatur

Location: GSW NE Sec. 10 Twp. 4 Rge. _____ (E) _____ (W) 27

Name of Field: _____ Total Depth: 4100

I have this date completed supervision of plugging of:

Lease Name: Crandell Well No. 1

Operator's Full Name: Time Petroleum Co

Complete Address: 815 Union Center Wichita, Kansas

Plugging Contractor Knight Casing Pulling & Globe Cementing

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 9 Month 11 Year 61

The above well was plugged as follows:

8 5/8" 240' circulated with cement - 4 1/2" 3700', with 150 sax cement

PB to 3620', - perforated 3593'

Filled with sand to 3580', set 3 sax cement with dump bailer - pulled 1278'

4 1/2" to 550', circulated hole with heavy mud through 4 1/2" at 550' (28 sax Gel)

displaced 20 sax cement through 4 1/2" at 550', heavy mud to 200', displaced

20 sax cement through 4 1/2" - heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 11/17/61
INV. NO. 4033-w