



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1974
CONSERVATION DIVISION
Wichita, Kansas
12-9-74

15-039-20295-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated.

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Tilden Well No. 1

Location CS/2-S/2-NE/4 Sec. 3 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3770'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30 AM Day 2 Month 12 Year 1974

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 110 Cu. Ft. cement
thru DP from 1350' to 1025'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickel
Well Plugging Supervisor

DATE 12/13/74
INV. NO. 455-W