

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20280-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1974

CONSERVATION DIVISION
Wichita, Kansas

2-25-74

Operator's Full Name KRM Petroleum Corporation,

Complete Address 403 Guaranty Bank Building, Denver, Colorado.

Lease Name Shinnick Well No. 1

Location NE-NE-SW Sec. 14 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3729'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 12:00 M Day 16 Month 2 Year 1974

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 110 Cu. Ft. cement
thru DP from 1350' to 1025'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickel
Well Plugging Supervisor

DATE 2/27/74
INV. NO. 8620-W