

KANSAS

*Y* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20204-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1970  
CONSERVATION DIVISION  
Wichita, Kansas

12-22-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Shimmick Well No. 1

Location SE-SE-SE Sec. 14 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 3665'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 3:30 PM Day 19 Month 12 Year 1970

The above well was plugged as follows:

265'--8 5/8" Surface casing, cement circulated with 190 Sx.  
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru  
DP from 1150' to 825'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*  
Well Plugging Supervisor

12/22/70  
3107-w