

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

15-039-00035-00-00

Lease Owner Harry Gore Address 400 Brown Bldg. Wichita, Ks.
(Applicant)

Lease (Farm Name) Brock Well No. 1

Well Location SW SW SW Sec. 22 Twp. 4 Rge. (E)-(W) 26

County Decatur Field Name (if any) _____

Total Depth 4085' Oil Gas Dry Hole X

Was well log filed with application? . If not, explain: _____

Log will be filed with application.

Date and hour plugging is desired to begin 6 a.m. 10-5-51

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

L. E. Bernd Address Box 229, McPherson, Kansas

Name of Plugging Contractor The Veeder Supply & Development Company

Address P. O. Box 201, Cherryvale, Kansas

Invoice covering assessment for plugging this well should be sent to

Harry Gore Address Brown Bldg, Wichita, Kansas

and payment will be guaranteed by applicant.

PLUGGING
FILE SEC. 24 4R
BOOK PAGE 115 LINE 15

OCT 12 1951

10-12-51

Floyd W. Hild
Applicant or Acting Agent

Date 10-5-51

15-039-00035-00-00

Company Harry Gore

Sec. 22 T. 4 R. 26

Farm Brock

No. 1

Loc. SW SW SW

County Decatur County, Kansas

Total Depth 4085'

Comm. 9-24-51

Comp. 10-5-51

Shot or Treated


Contractor Veeder Supply Company

Drilled with Rig - D

Issued

No. of Days - 12

No. of Bits -



Casing
 20 in. 10 in
 15 1/2 8 1/4
 12 1/2 6 5/8
 13 3/8 5 3/16

Run 218' of 8-5/8" Csg. Cemented with 150 sacks cement.

Elevation

Production

Figures Indicate Bottom of Formation

Sand Shale Shells	0	218	218
Blue Shale	218	700	482
Shale Shells	700	1120	420
Shale Sand	1120	1450	330
Shale Shells	1450	1525	75
Sand Shale	1525	1605	80
Shale Shells Sand	1605	2050	445
Red Bed Shale	2050	2198	148
Anhydrite	2198	2233	35
Shale Shells	2233	2395	162
Lime Shale	2395	3080	685
Lime	3080	3235	155
Lime Shale	3235	3520	285
Lime	3520	3650	130
Lime Shale	3650	3695	45
Lime	3695	3805	110
Lime Shale	3805	4010	205
Shale Conglomerate	4010	4070	60
Lime	4070	4085	15
Total Depth	4085'		

<u>Tons:</u>	
Topeka	- 3391'
Heenber	- 3587'
Brown Lime	- 3613'
Lansing K.C.	- 3627'
Base K. G.	- 3824'
Conglomerate	- 3993'
Arbuckle	- 4029'

Plugged @ 200' with 155 sacks cement.
 Plugged @ 40' with 10 sacks cement.

PLUGGING
 FILE SEC 22 T. 4 R. 26
 BOOK PAGE 115 LINE 15

10-12-51



15-039-00035-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

October 9, 1951

Well No.	1
Lease	Brock
Description	SW SW SW 22-4-26W
County	Decatur
File No.	115-15

Mr. Harry Gore
400 Brown Bldg.
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY:

J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR