

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20188-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tomlinson Oil Company, Incorporated,

Complete Address 1125 Wichita Plaza, Wichita, Kansas.

Lease Name Tilden Well No. 1

Location SE-NE-NE Sec. 3 Twp. 4 Rge. (E) (W) 27

County Decatur Total Depth 4045'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Aspen Drilling Company,

Address Box#783, Great Bend, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 24 Month 11 Year 1970

The above well was plugged as follows:

233'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/1/70
INV. NO. 2959-4