

15-147-19094-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Wilkinson Drilling, Inc. & Midwestern Supply Co., Inc.

Complete Address 710 Union Nat'l. Bldg., Wichita, Kansas 67202

Lease Name Lutz Well No. # 1

Location NE SE SW Sec. 35 Twp. 4 Rge. 20 (E) (W)

County Phillips Total Depth 3424

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Company

Address Box 221, Great Bend, Kansas 67530 License No. # 49

Operation Completed: Hour 2 P.M. Day 30 Month 6 Year 1969

The above well was plugged as follows:

8 5/8" 246' Cwc. 5 1/2" 3424' Perf. 3356'.

Sanded hole back to 3320' & dumped 5 sax cement with dump bailer. Pulled pipe.

Squeezed well with 5 sax hulls, 20 sax mud, & 120 sax cement with Allied Cementing

Company's pump truck, cementing from 450' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1969

CONSERVATION DIVISION
Wichita, Kansas

7-3-69

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/3/69

INV. NO. 41-W

Signed: [Signature]
Well Plugging Supervisor